STANDARD JOINT PERMIT APPLICATION

HAH

United States Army Corps of Engineers (USACE) - Norfolk District

803 Front Street, ATTN: CENAO-WR-R

Norfolk, Virginia 23510-1011

Phone: (757) 201-7652, Fax: (757) 201-7678

Website: http://www.nao.usace.army.mil/Missions/Regulatory.aspx



Virginia Marine Resources Commission (VMRC)
Habitat Management Division
380 Fenwick Road, Building 96
Fort Monroe, VA 23651

Phone: (757) 247-2200, Fax: (757) 247-8062

Website: http://www.mrc.virginia.gov/hmac/hmoverview.shtm



Virginia Department of Environmental Quality (DEQ)
Virginia Water Protection Permit Program
Post Office Box 1105
Richmond, Virginia 23218
Phone: (804) 698-4000

Websites: http://www.deq.virginia.gov/ http://www.deq.virginia.gov/Locations.aspx

The following instructions and information are designed to assist you in applying for permits from federal, state, and local regulatory agencies for work in waters and/or wetlands within the Commonwealth of Virginia. The intent is to provide general information on the permit process, not to act as a complete legal and technical reference. Refer to the applicable laws, regulations, and/or guidance materials of each agency for a complete understanding of each agency's application requirements.

JOINT PERMIT APPLICATION PROCESS

The Joint Permit Application (JPA) process and Standard JPA form are used by the United States Army Corps of Engineers (USACE), the Virginia Marine Resources Commission (VMRC), the Virginia Department of Environmental Quality (DEQ), and the Local Wetlands Boards (LWB) for permitting purposes involving water, wetlands, and dune/beach resources, including water supply and water withdrawals projects (as defined in DEQ Regulation 9 VAC 25-210).

The Tidewater Joint Permit Application form is used for proposed private or commercial aquaculture projects and most commercial and noncommercial projects in **tidal waters**, **tidal wetlands**, **and coastal primary sand dunes and beaches in Virginia** that require the review and/or authorization by the LWB, the VMRC, the DEQ, and/or the USACE. The Tidewater JPA may be downloaded from the same web page on which the Standard JPA is located: http://www.nao.usace.army.mil/Missions/Regulatory/JPA.aspx. If using the Tidewater JPA, follow the instructions provided with that form.

Please note that some health departments and local agencies, such as local building officials and erosion and sediment control authorities, <u>do not</u> use the Joint Permit Application process or forms and may have different informational requirements. The applicant is responsible for contacting these agencies for information regarding those permitting requirements.

REGULATORY AUTHORITIES OF PARTICIPATING AGENCIES: The USACE regulates activities in waters of the United States, including wetlands, under Section 404 of the Clean Water Act (33 U.S.C. §1344), Section 10 of the Rivers and Harbors Act of 1899 (33 U.S.C. §403), and Section 103 of the Marine Protection Research and Sanctuaries Act of 1972 (33 U.S.C. §1413).

The VMRC regulates activities on state-owned submerged lands, tidal wetlands, and dunes/beaches under Code of Virginia Title 28.2, Chapters 12, 13, and 14.

The DEQ regulates activities in state surface waters and wetlands under Section 401 of the Clean Water Act (33 U.S.C. §1341), under State Water Control Law (Code of Virginia Title 62.1), and Virginia Administrative Code Regulations 9VAC25-210 et seq., 9VAC25-660 et seq., 9VAC25-670 et seq., 9VAC25-680 et seq., and 9VAC25-690 et seq.

The LWBs regulate activities in tidal wetlands and dunes/beaches under Code of Virginia Title 28.2, Chapters 13 and 14.

LOCAL WETLANDS BOARD CONTACT INFORMATION: Links to LWB information on the Web can be found at http://ccrm.vims.edu/permits_web/guidance/local_wetlands_boards.html.

USACE FIELD OFFICE INFORMATION AND DEQ REGIONAL OFFICE INFORMATION: Answers to technical questions and detailed information about specific aspects of the various permit programs may be obtained from the USACE field office in your project area (please refer to the Contact Information on the Regulatory web page at: http://www.nao.usace.army.mil/Missions/Regulatory.aspx or call 757-201-7652), or from the DEQ regional office in your project area (please refer to http://www.deq.virginia.gov/Locations.aspx or call 804-698-4000). Applicants may also seek assistance with completing the informational requirements and/or submittals from private consulting and/or engineering firms for hire.

CHESAPEAKE BAY PRESERVATION ACT INFORMATION: Development within the 84 Counties, Cities, and Towns of "Tidewater Virginia" (as defined in §62.1-44.15:68 of the Code of Virginia) is subject to the requirements of the Chesapeake Bay Preservation

Application Revised: October 2019

Act. If your project is located in a Bay Act locality and will involve activities, including land disturbance or removal of vegetation, within a designated Resource Protection Area (RPA), these actions will require approval from your local government and completion of Appendix C. The individual localities, not the DEQ, USACE, or Local Wetlands Boards, are responsible for enforcing Bay Act requirements and, therefore, local approval for any activity in an RPA is not granted through this JPA process. Each Tidewater locality has adopted a program based on the Chesapeake Bay Preservation Act and the Chesapeake Bay Preservation Area Designation & Management Regulations.

The Act and regulations require Bay Act local governments to administer specific criteria for the use, development and redevelopment of land within locally designated Chesapeake Bay Preservation Areas. Since the requirements of the Bay Act may affect the ultimate design and construction of projects, applicants should contact their local government as early in the process as possible, in order to ensure that these requirements are considered early in the permitting process, and to avoid unnecessary and costly delays. Individual localities will request information regarding existing vegetation within the RPA as well as a description and site drawings of any proposed activity within the RPA. This information will be used by local staff charged with ensuring compliance with the Bay Act during the local approval process. Any use, development and redevelopment or land disturbance within the RPA must receive local approval PRIOR to the initiation of any land disturbance.

To determine if your project is located in a Bay Act locality (see map on page 31 or http://www.deq.virginia.gov/Programs/Water/ChesapeakeBay/ChesapeakeBayPreservationAct/LocalGovernmentOrdinances.aspx), learn more about Bay Act requirements, or find local government contacts, please visit the Virginia Department of Environmental Quality at http://www.deq.virginia.gov/Programs/Water/ChesapeakeBay/ChesapeakeBayPreservationAct.aspx.

HOW TO APPLY

Sections A through D below provide a general list of information and drawings that are required, depending on the type of project being proposed. Prepare all required drawings or sketches as detailed in the lists provided in Appendix D (Drawings) and according to the sample drawings provided in Appendix D.

Application materials should be submitted to VMRC:

- 1. If by mail or courier, use the address on page 1.
- 2. If by electronic mail, address the package to: JPA.permits@mrc.virginia.gov. The application must be provided in the .pdf format.

When completing this form, use the legal name of the applicant, agent, and/or property owner. For DEQ application purposes, *legal name* means the full legal name of an individual, business, or other organization. For an individual, the legal name is the first name, middle initial, last name, and suffix. For an entity authorized to do business in Virginia, the legal name is the exact name set forth in the entity's articles of incorporation, organization or trust, or formation agreement, as applicable. Also provide the name registered with the State Corporation Commission, if required to register. DEQ issues a permit or grants coverage to the so-named individual or business, who becomes the 'permittee'. Correspondence from some agencies, including permits, authorizations, and/or coverage, may be provided via electronic mail. If the applicant and/or agent wish(es) to receive their permit via electronic mail, please remember to include an e-mail address at the requested place in the application.

A. APPLICATIONS FOR PROJECTS INVOLVING IMPACTS TO <u>TIDAL</u> WATERS, WETLANDS, AND DUNES/BEACHES (INCLUDING SHORELINE STABILIZATION, PIERS, MARINAS, BEACH NOURISHMENT, BOATHOUSES, BOAT LIFTS, BREAKWATERS, AQUACULTURE ACTIVITIES, DREDGING, ETC.) SHOULD INCLUDE THE FOLLOWING:

- All applicable portions of Sections 1 through 26 of the JPA, including necessary attachments, information required for projects located in CBPA localities as required in Appendix C (a map of CBPA localities can be found on page 31).
- Adjacent Property Owner's Acknowledgement Forms⁽¹⁾, as detailed in Appendix A or the name and address of the adjacent landowners.
- An analysis of the functions of wetlands proposed to be impacted may be required by DEQ. (3).
- A set of 8 ½ x 11 inch drawings. If you cannot include all of your project site on one page at a scale no smaller than 1" = 200', you **must** submit a set of 8 ½ x 11 inch match-line drawings **and** a set of large-sized drawings at a scale no smaller than 1" = 200'. If oversized drawings are used, attach **five** copies of the oversized drawings to your application.
- In order for projects requiring LWB authorization to be considered complete, applications must include the following information (per Virginia Code 28.2-1302): "The permit application shall include the following: the name and address of the applicant; a detailed description of the proposed activities; a map, drawn to an appropriate and uniform scale, showing the area of wetlands directly affected, the location of the proposed work thereon, the area of existing and proposed fill and excavation, the location, width, depth and length of any proposed channel and disposal area, and the location of all existing and proposed structures, sewage collection and treatment facilities, utility installations, roadways, and other related appurtenances of facilities, including those on the adjacent uplands; a description of the type of equipment to be used and the means of access to the activity site; the names and addresses of record of adjacent land and known claimants of water rights in or adjacent to the wetland of whom the applicant has notice; an estimate of cost; the primary purpose of the project; and secondary purpose of the proposed project; a complete description of measures to be taken during and after alteration to reduce detrimental offsite effects; the completion date of the proposed work, project, or structure; and such additional materials and documentation as the wetlands board may require."

B. APPLICATIONS FOR PROJECTS INVOLVING IMPACTS TO NONTIDAL WATERS AND/OR WETLANDS AND:

1) WHERE AUTHORIZATION UNDER STATE PROGRAM GENERAL PERMIT (SPGP) IS REQUESTED:

Programmatic general permits may be issued by the USACE in situations where a state, regional, or local authority has a regulatory program in place that provides similar review and regulation of activities in waters as does the USACE. In such cases, the programmatic general permit allows the state, region, or locality to provide the federal authorization, thus avoiding unnecessary duplication of effort by multiple regulatory authorities. In Virginia, DEQ provides authorization for certain activities regulated by the USACE through the State Program General Permit (SPGP). DEQ's authorization under the SPGP is a separate action from that providing coverage under any Virginia Water Protection permit. Certain Residential/Commercial/Institutional Development activities and Linear Transportation activities will be considered for coverage under the current SPGP. Details about the current SPGP can be found at http://www.nao.usace.army.mil/Missions/Regulatory/RBregional.aspx.

- Mark the "SPGP" checkbox on page 7 of this application.
- All applicable portions of Sections 1 through 26 of the JPA, including necessary attachments.
- ❖ A conceptual compensatory mitigation plan⁽²⁾.
- A copy of the confirmed jurisdictional determination or confirmed delineation, including a waters and wetlands boundary map and data sheets⁽³⁾.
- All information required for projects located in CBPA localities as required in Appendix C (a map of CBPA localities can be found on page 31).
- ❖ A copy of the FEMA flood insurance rate map or FEMA-approved local floodplain map for the project site (not applicable to <0.1 acre and < 300 linear feet projects by either USACE or DEQ).
- A set of 8 ½ x 11 inch drawings. If you cannot include all of your project site on one page at a scale no smaller than 1" = 200', you **must** submit a set of 8 ½ x 11 inch match-line drawings **and** a set of large-sized drawings at a scale no smaller than 1"= 200'. If oversized drawings are used, attach **five** copies of the oversized drawings to your application.

2) WHERE NO SPGP IS REQUESTED:

- All applicable portions of Sections 1 through 26 of the JPA, including necessary attachments.
- ❖ A conceptual compensatory mitigation plan⁽²⁾.
- A copy of the confirmed jurisdictional determination or confirmed delineation, including a waters and wetlands boundary map and data sheets⁽³⁾.
- All information required for projects located in CBPA localities as required in Appendix C (a map of CBPA localities can be found on page 31), and a copy of the FEMA flood insurance rate map or FEMA-approved local floodplain map for the project site.
- An analysis of the functions of wetlands proposed to be impacted may be required by DEQ (4).
- A set of 8 ½ x 11 inch drawings. If you cannot include all of your project site on one page at a scale no smaller than 1" = 200', you **must** submit a set of 8 ½ x 11 inch match-line drawings **and** a set of large-sized drawings at a scale no smaller than 1"= 200'. If oversized drawings are used, attach **five** copies of the oversized drawings to your application.

C. APPLICATIONS FOR PROJECTS INVOLVING SURFACE WATER WITHDRAWALS or FERC LICENSE OR RELICENSE ASSOCIATED WITH A SURFACE WATER WITHDRAWAL:

- Mark the "DEQ Reapplication" checkbox on page 7 of this application and provide the current/existing permit number.
- All applicable portions of Sections 1 through 26 of the JPA, including necessary attachments.
- All applicable portions of Part A and B above if the project involves wetland and/or stream impacts.
- Copy of any pre-application review panel documentation and summary of the issues raised
- For new or expanded surface water withdrawals proposing to withdraw 90 million gallons a month or greater, a summary of the steps taken to seek public input as required by 9VAC25-210-320 and an identification of the issues raised during the course of the public information meeting process.

D. ANY APPLICATIONS USING THE JPA FORM AS A PRE-CONSTRUCTION NOTIFICATION (PCN) FOR A USACE NATIONWIDE PERMIT:

- Mark the "PCN" checkbox on page 7 of this application and insert the number of the intended Nationwide permit. If you fail to mark this box, the PCN will be deemed incomplete and the USACE 45-day time clock will not start.
- All applicable portions of Sections 1 through 26 of the JPA, including necessary attachments and all information required for projects located in CBPA localities as required in Appendix C (a map of CBPA localities can be found on page 31).
- A set of 8 ½ x 11 inch drawings. If you cannot include all of your project site on one page at a scale no smaller than 1" = 200', you **must** submit a set of 8 ½ x 11 inch match-line drawings **and** a set of large-sized drawings at a scale no smaller than 1"= 200'. If oversized drawings are used, attach **five** copies of the oversized drawings to your application.

WHAT HAPPENS NEXT

Upon receipt of an application, VMRC will assign a permit application number to the JPA and will then distribute a copy of the application and any plan copies submitted to the other regulatory agencies that are involved in the JPA process. All agencies will conduct separate but concurrent reviews of your project. Please be aware that each agency must issue a separate permit (or a notification that no permit is required). Note that in some cases, DEQ may be taking an action on behalf of the USACE, such as when the State Program General Permit (SPGP) applies. Make sure that you have received all necessary authorizations, or documentation that no permit is required, from each agency prior to beginning the proposed work.

During the JPA review process, site inspections may be necessary to evaluate a proposed project. Failure to allow an authorized representative of a regulatory agency to enter the property, or to take photographs of conditions at the project site, may result in either the withdrawal or denial of your permit application.

For certain federal and state permit applications, a public notice is published in a newspaper having circulation in the project area, is mailed to adjacent and/or riparian property owners, and/or is posted on the agency's web page. The public may comment on the project during a designated comment period, if applicable, which varies depending upon the type of permit being applied for and the issuing agency. In certain circumstances, the project may be heard by a governing board, such as a Local Wetlands Board, the State Water Control Board, or VMRC in cases where a locality does not have a wetlands board. You may be responsible for bearing the costs for advertisement of public notices.

Public hearings that are held by VMRC occur at their regularly scheduled monthly commission meetings under the following situations: Protested applications for VMRC permits which cannot be resolved; projects costing over \$500,000 involving encroachment over state-owned subaqueous land; and all projects affecting tidal wetlands and dunes/beaches in localities without a LWB. All interested parties will be officially notified regarding the date and time of the hearing and Commission meeting procedures. The Commission will usually make a decision on the project at the meeting unless a decision for continuance is made. If a proposed project is approved, a permit or similar agency correspondence is sent to the applicant. In some cases, notarized signatures, as well as processing fees and royalties, are required before the permit is validated. If the project is denied, the applicant will be notified in writing.

PERMIT APPLICATION OR OTHER FEES

<u>DO NOT send any fees with the JPA</u>. VMRC is not responsible for accounting for fees required by other agencies. Please consult agency websites or contact agencies directly for current fee information and submittal instructions.

- USACE: Permit application fees are required for USACE Individual (Standard) permits. A USACE project manager will contact you regarding the proper fee and submittal requirements.
- ❖ DEQ: Permit application fees required for Virginia Water Protection permits while detailed in 9VAC25-20 are conveyed to the applicant by the applicable DEQ office (http://www.deq.virginia.gov/Locations.aspx). Complete the Permit Application Fee Form and submit it per the instructions listed on the form. Instructions for submitting any other fees will be provided to the applicant by DEQ staff.
- VMRC: An application fee of \$300 may be required for projects impacting tidal wetlands, beaches and/or dunes when VMRC acts as the LWB. VMRC will notify the applicant in writing if the fee is required. Permit fees involving subaqueous lands are \$25.00 for projects costing \$10,000 or less and \$100 for projects costing more than \$10,000. Royalties may also be required for some projects. The proper permit fee and any required royalty is paid at the time of permit issuance by VMRC. VMRC staff will send the permittee a letter notifying him/her of the proper permit fees and submittal requirements.
- LWB: Permit fees vary by locality. Contact the LWB for your project area or their locality website for fee information and submittal requirements. Contact information for LWB may be found at http://ccrm.vims.edu/permits-web/quidance/local-wetlands-boards.html.

INFORMATION REGARDING THREATENED OR ENDANGERED SPECIES

In order to find preliminary information regarding federal or state threatened or endangered species on your project site, you may contact the following four agencies:

United States Fish and Wildlife Service	NOAA Fisheries Greater Atlantic Region Fisheries Office
6669 Short Lane	National Marine Fisheries Service
Gloucester, Virginia 23061	55 Great Republic Drive
Voice: (804) 693-6694	Gloucester, MA 01930
Fax: (804) 693-9032	Voice: (978) 281-9300
http://virginiafieldoffice.fws.gov/	https://www.greateratlantic.fisheries.noaa.gov/contact_us/index.ht
	<u>ml</u>
Project Review Coordinator	Virginia Department of Game and Inland Fisheries
Virginia Department of Conservation and Recreation	Environmental Services Section
Natural Heritage Division	4010 West Broad Street
217 Governor Street	Richmond, Virginia 23230-1104
Richmond, Virginia 23219	(804) 367-1000
Voice: (804) 786-7951	http://www.dgif.virginia.gov/wildlife/
Fax: (804) 371-2674	
http://www.dcr.virginia.gov/natural_heritage/index.shtml	

INFORMATION REGARDING FEMA-MAPPED FLOODPLAINS

You may obtain "Online Hazard Maps" for FEMA-mapped floodplains by visiting https://hazards.fema.gov/femaportal/wps/portal. Local governments also keep paper copies of FEMA maps on hand.

FOOTNOTES

- (1) Adjacent Property Owner Notification: When determining whether to grant or deny any permit for the use of state-owned submerged lands, the VMRC must consider, among other things, effects of a proposed project on adjacent or nearby properties. Discussing the proposed project with these property owners can be done on your own using the forms in Appendix A of this package. Local Wetlands Boards (LWB) must also consider the effects on adjacent properties and notify adjoining property owners of the required public hearings for all applications. The completed forms will assist VMRC and LWB in processing the application. The forms in Appendix A may be photocopied if more copies are needed. This information will not be used by DEQ to meet the requirements of notifying riparian land owners.
- (2) Compensatory mitigation plans. Conceptual compensatory mitigation plans, when required, should include all information stipulated in Sections 80 B and 116 F of DEQ Regulation 9VAC25-210 for Virginia Water Protection individual permit applicants, or in Sections 60 B and/or 70 of DEQ Regulations 9VAC25-660, 9VAC25-670, 9VAC25-680, or 9VAC25-690 for Virginia Water Protection general permit coverage applicants. Regulations may be obtained from DEQ's web site at http://www.deq.virginia.gov/Programs/Water/WetlandsStreams.aspx. Information on wetland and stream compensatory mitigation is available at http://www.deq.virginia.gov/Programs/Water/WetlandsStreams/Mitigation.aspx. The SPGP applicant is required to provide a conceptual mitigation plan in accordance with the current SPGP (http://www.nao.usace.army.mil/Missions/Regulatory/RBregional.aspx). Final compensatory mitigation plans will be required prior to commencement of impacts to waters and/or wetlands on your project site. If no mitigation is planned, submit a detailed statement as to why no mitigation is planned. For projects requiring a LWB or VMRC tidal wetlands permit, please consult the VMRC Wetlands Mitigation-Compensation Policy and Supplemental Guidelines: 4 VAC 20-390 at http://www.mrc.virginia.gov/regulations/regindex.shtm.
- (3) Wetland and waters boundary delineation map: Wetlands/waters delineations must be performed using the USACE "Wetland Delineation Manual, Technical Report Y-87-1, January 1987, Final Report" (Federal Manual) and if applicable, the current version of the Regional Supplement to the Corps of Engineers Wetlands Delineation Manual (Atlantic and Gulf Coastal Plain Region or Eastern Mountains and Piedmont Region. The SPGP applicant is required to provide a Corps-confirmed jurisdictional determination or Corps-confirmed delineation approved for use with a permit application, in accordance with the current SPGP (http://www.nao.usace.army.mil/Missions/Regulatory/RBregional.aspx). Contact the appropriate USACE District office or field office to obtain a delineation confirmation by referencing the Contact Information on the Regulatory web page at: http://www.nao.usace.army.mil/Missions/Regulatory.aspx or call the Regulator of the Day (ROD) at 757-201-7652. If a USACE confirmation is not available at the time of application, it must be submitted as soon as it becomes available during the DEQ permit review. For DEQ application purposes, the requirements for delineations apply to all applications, regardless of the amount of impacts. The information to be submitted is detailed in 9VAC25-210-80 B 1 h and is the same regardless of the type of VWP permit being sought.
- (4) An analysis of the functions of wetlands, when required for DEQ permitting purposes, shall assess water quality or habitat metrics and shall be coordinated with DEQ in advance of conducting the analysis. For DEQ permitting purposes, please refer to the requirements in 9VAC25-210-80 C, which are the same regardless of the type of VWP permit being sought.

TABLE OF CONTENTS

Section 1:	Applicant, Agent, Property Owner, and Contractor Information	7
Section 2:	Project Location Information	8
Section 3:	Description of Project, Purposes, Need, Use(s), and Alternatives	9
Section 4:	Project Costs	10
Section 5:	Public Notification	10
Section 6:	Threatened and Endangered Species Information	10
Section 7:	Historic Resources Information.	10
Section 8:	Wetlands, Waters, and Dunes/Beaches Impact Information	11
Section 9:	Applicant, Agent, Property Owner and Contractor Certifications	12
Section 10:	Private Piers, Marginal Wharves, and Uncovered Boatlifts	14
Section 11:	Boathouses, Gazebos, Covered Boat Lifts, and Other Roofed Structures Over Waterways	14
Section 12:	Marinas and Commercial, Governmental, and Community Piers	14
Section 13:	Free Standing Mooring Piles, Osprey Nesting Poles, Mooring Buoys, and Dolphins	15
Section 14:	Boat Ramps	15
Section 15:	Tidal/Nontidal Shoreline Stabilization Structures	15
Section 16:	Beach Nourishment	16
Section 17:	Dredging, Mining, and Excavating	17
Section 18:	Fill and Other Structures in Wetlands or Waters, or on Dunes/Beaches	18
Section 19:	Nontidal Stream Channel Modifications for Restoration or Enhancement, or Temporary or Permanent	
	Relocations	18
Section 20:	Utility Crossings	19
Section 21:	Road Crossings	20
Section 22:	Impoundments, Dams, and Stormwater Management Facilities	20
Section 23:	Outfalls Not Associated with Proposed Water Withdrawal Activities	21
Section 24:	Intakes, Outfalls, and Water Control Structures	22
Section 25:	Water Withdrawal Use(s), Need, and Alternatives	24
Section 26:	Public Comments/Issues for Major Water Withdrawals or Interbasin Transfers	26
Appendix A:	Adjacent Property Owner's Acknowledgement Forms	27
Appendix B:	Regional Permit 17 Checklist	29
Appendix C:	Chesapeake Bay Preservation Act Information.	30
Appendix D:	Sample Drawings	32

				FOR	AGENC	Y USE ONL	Υ			
					102.110	Notes:				
JPA#										
						<u> </u>				
				ΔΡ	PI IC	CANTS				
LEASE PRINT	OR TYPE ALL A	NSWEF	RS. If a c				ır project, plea	ase print N/	'A (not app	licable) in the space
rovided. <i>If add</i>	ditional space is n	eeded,	attach e				f paper.			
Pro Const	ruction Notification	(DCNI)	SP			at apply				
NWP#_	ruction Notification	i (PCN)	38	GP		EQ Reapplicing permit nu			iving feder roviding fu	
RP # 05								Agency p	Toviding id	
(For NWPs & F permit writer w	RP 05 ONLY - No DE ill be assigned)	Q-VWP								
Regional P	ermit 17 Checklist	(RP-17)		1					
PREV	OUS ACTIONS RI									
Historical i	nformation for past pe									
						erms/newper				
Agency	Action /	Activity				t number,	Date of A	ction	If denied, g	jive reason for denial
						non-reporting le permits				
				previou	ısly used 13)	(e.g., NWP				
					13)					
1 APPLICAT	NT AGENT PROF	PERTY	OWNER	AND CO	NTRAC		PMATION			
The applicar	nt, AGENT, PROF nt(s) is/are the leg	al entit	y to whi	ch the per	rmit ma	y be issued	d (see How to			
										ertake the activity. vide the company
name that is	registered with the	ne Stat	e Corpoi	ation Cor	nmissio	on (SCC), o	r indicate no	registratio	on with the	e SCC.
Legal Name(s) of Applicant(s)					Agent (if a	pplicable)			
Mailing addre	ess					Mailing ad	dress			
0''			I a			0			10: :	T 715 0 1
City			State	ZIP Cod	е	City			State	ZIP Code
Phone numb	er w/area code	Fax				Phone nur	mber w/area o	code F	- Fax	
	o, a. oa ooao									
Mobile		E-ma	il			Mobile		E	E-mail	
	ation Commission I	Name a	nd ID nu	mber (if			oration Com	mission Na	me and ID	number (if
applicable)						applicable	•			
	nits or permit autl lectronic mail, ple						mail. If the a	pplicant w	vishes to r	receive their
periint via ei	ecuonic man, pie	ase pro	viue all	e-man au	ui c oo li					

1. APPLICANT, AGENT, PROF	PERTY	OWNER	, AND CONTRA	CTOR INFORMATIO	N (Continued)				
Property owner(s) legal name, if different from applicant			Contractor, if know	Contractor, if known					
Mailing address				Mailing address					
City		State	ZIP code	City		State	ZIP code		
Phone number w/area code	Fax	l		Phone number w/a	area code	Fax	1		
Mobile	E-ma	il		Mobile		E-mail			
State Corporation Commission applicable)	Name a	ınd ID nu	mber (if	State Corporation	Commission N	lame ID nun	nber (if applicable)		
2. PROJECT LOCATION INFO (Attach a copy of a detailed m boundary, so that it may be lo	ap, su cated t	ch as a l for inspe							
area if the SPGP box is checked on Page 7.) Street Address (911 address if available)			City/County/ZIP Co	City/County/ZIP Code					
Subdivision				Lot/Block/Parcel #	Lot/Block/Parcel #				
Name of water body(ies) within	project	boundari	es and drainage	e area (acres or square	e miles).				
Tributary(ies) to: Basin: (<i>Example: Basin: <u>James</u> River</i>		Sub-basir		ver)					
Special Standards (based on D				·					
Project type (check one)				private, non-commerci ommunity, commercia er withdrawal					
Latitude and longitude at center (Example: 37.33164/-77.68200)		ect site (d	decimal degrees):	/	-			
USGS topographic map name:					_				
8-digit USGS Hydrologic Unit Code (HUC) for your project site (See http://cfpub.epa.gov/surf/locate/index.cfm): If known, indicate the 10-digit and 12-digit USGS HUCs (see http://consapps.dcr.virginia.gov/htdocs/maps/HUExplorer.htm):									
Name of your project (Example.	Water	Creek dr	iveway crossing)					
Is there an access road to the p	roject?	Yes _	No. If yes, ch	eck all that apply: p	oublic privat	te improv	red unimproved		
Total size of the project area (in	acroc):								

2. PROJECT LOCATION INFORMATION (Continued)	
Provide driving directions to your site, giving distances from the be	est and nearest visible landmarks or major intersections:
Does your project site cross boundaries of two or more localities (If so, name those localities:	i.e., cities/counties/towns)? Yes No
 USE(S), AND ALTERNATIVES CONSIDERED (Attach additing the purpose and need must include any new development or residual land. Describe the physical alteration of surface waters, including the and hydraulic dredging, when applicable, and whether or not year). Include a description of alternatives considered and measures wetlands, to the maximum extent practicable. Include factors alternative project layout and design, alternative locations, locations, include both alternative routes and alternative. 	r expansion of an existing land use and/or proposed future use of the use of pilings (#, materials), vibratory hammers, explosives, tree clearing will occur (include the area in square feet and time of staken to avoid or minimize impacts to surface waters, including such as, but not limited to, alternative construction technologies, cal land use regulations, and existing infrastructure native construction methodologies considered ithdrawals, or projects that will alter in stream flows, include the
Date of proposed commencement of work (MM/DD/YYYY)	Date of proposed completion of work (MM/DD/YYYY)
Are you submitting this application at the direction of any state, local, or federal agency?YesNo	Has any work commenced or has any portion of the project for which you are seeking a permit been completed? Yes No
If you answered "yes" to either question above, give details stating performed the work, and which agency (if any) directed you to sub differentiate between completed work and proposed work on your	omit this application. In addition, you will need to clearly
Are you aware of any unresolved violations of environmental law of (If yes, please explain)	or litigation involving the property?YesNo

4. PROJECT COSTS								
Approximate cost of the entire project, including materials and labor: \$ Approximate cost of only the portion of the project affecting state waters (channelward of mean low water in tidal areas and below ordinary high water mark in nontidal areas): \$								
5. PUBLIC NOTIFICATION (Attach additional sheets if neces	sarv)						
5. PUBLIC NOTIFICATION (Attach additional sheets if necessary) Complete information for all property owners adjacent to the project site and across the waterway, if the waterway is less than 500 feet in width. If your project is located within a cove, you will need to provide names and mailing addresses for all property owners within the cove. If you own the adjacent lot, provide the requested information for the first adjacent parcel beyond your property line. Per Army Regulation (AR 25-51) outgoing correspondence must be addressed to a person or business. Failure to provide this information may result in a delay in the processing of your application by VMRC.								
Property owner's name	Mailing address	City	State	ZIP code				
Name of newspaper having ger Address and phone number (inc newspaper	neral circulation in the area of the cluding area code) of	project:						
Have adjacent property owners	been notified with forms in Appe	endix A?YesNo	o (attach copies of distri	buted forms)				
C. TUDEATENED AND ENDA	NCEDED CRECIES INFORMAT	ION						
O. IRREATENED AND ENDA	NGERED SPECIES INFORMAT	ION						
Please provide any information concerning the potential for your project to impact state and/or federally threatened and endangered species (listed or proposed). Attach correspondence from agencies and/or reference materials that address potential impacts, such as database search results or confirmed waters and wetlands delineation/jurisdictional determination. Include information when applicable regarding the location of the project in Endangered Species Act-designated or -critical habitats. Contact information for the U.S. Fish and Wildlife Service, National Oceanic and Atmospheric Administration, Virginia Dept. of Game and Inland Fisheries, and the Virginia Dept. of Conservation and Recreation-Division of Natural Heritage can be found on page 4 of this package.								
7. HISTORIC RESOURCES IN	IFORMATION							
Note: Historic properties include but are not limited to archeological sites, battlefields, Civil War earthworks, graveyards, buildings, bridges, canals, etc. Prospective permittees should be aware that section 110k of the NHPA (16 U.S.C. 470h-2(k)) prevents the USACE from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of Section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless the USACE, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant.								
	ted within or adjacent to the projection of the historic							
	tures 50 years old or older locate lowing the location of these build			_ Uncertain				
Is your project located within a	historic district? Yes	_ No Uncertain						

If Yes, please indicate which district:

7. HISTORIC RESOURCE	S INFORMATION (C	Continued)								
Has a survey to locate arch		r historic structures b	peen carried out on th	ne property?						
If Yes, please provide the fo	If Yes, please provide the following information: Date of Survey:									
Name of firm:					-					
Is there a report on file with	the Virginia Departm	nent of Historic Reso	urces? Yes _	NoUncerta	n					
Title of Cultural Re	esources Manageme	nt (CRM) report:								
Was any historic p	roperty located?	Yes No	_ Uncertain							
8. WETLANDS, WATERS	, AND DUNES/BEA	CHES IMPACT INFO	DRMATION							
Report each impact site in ensure that the associated dredging, mining, and except the state of	d project drawings	clearly depict the lo								
	Impact site number 1	Impact site number 2	Impact site number 3	Impact site number 4	Impact site number 5					
Impact description (use all that apply): F=fill EX=excavation S=Structure T=tidal NT=non-tidal TE=temporary PE=permanent PR=perennial IN=intermittent SB=subaqueous bottom DB=dune/beach IS=hydrologically isolated V=vegetated NV=non-vegetated MC=Mechanized Clearing of PFO (Example: F, NT, PE, V)										
Latitude / Longitude (in decimal degrees)										
Wetland/waters impact area (square feet / acres)										
Dune/beach impact area (square feet)										
Stream dimensions at impact site (length and average width in linear feet, and area in square feet)										
Volume of fill below Mean High Water or Ordinary High Water (cubic yards)										

8. WETLANDS/WATERS	IMPACT INFORMA	TION (Continued)		
Cowardin classification of impacted wetland/water or geomorphological classification of stream Example wetland: PFO; Example stream: 'C' channel and if tidal, whether vegetated or non-vegetated wetlands per Section 28.2-1300 of the Code of Virginia				
Average stream flow at site (flow rate under normal rainfall conditions in cubic feet per second) and method of deriving it (gage, estimate, etc.)				
Contributing drainage area in acres or square miles (VMRC cannot complete review without this information)				
DEQ classification of impacted resource(s): Estuarine Class II Non-tidal waters Class III Mountainous zone waters Class IV Stockable trout waters Class V Natural trout waters Class VI Wetlands Class VII https://law.lis.virginia.gov				

For DEQ permitting purposes, also submit as part of this section a wetland and waters boundary delineation map – see (3) in the Footnotes section in the form instructions.

For DEQ permitting purposes, also submit as part of this section a written disclosure of all wetlands, open water, or streams that are located within the proposed project or compensation areas that are also under a deed restriction, conservation easement, restrictive covenant, or other land-use protective instrument.

9. APPLICANT, AGENT, PROPERTY OWNER, AND CONTRACTOR CERTIFICATIONS

READ ALL OF THE FOLLOWING CAREFULLY BEFORE SIGNING

PRIVACY ACT STATEMENT: The Department of the Army permit program is authorized by Section 10 of the Rivers and Harbors Act of 1899, Section 404 of the Clean Water Act, and Section 103 of the Marine Protection Research and Sanctuaries Act of 1972. These laws require that individuals obtain permits that authorize structures and work in or affecting navigable waters of the United States, the discharge of dredged or fill material into waters of the United States, and the transportation of dredged material for the purpose of dumping it into ocean waters prior to undertaking the activity. Information provided in the Joint Permit Application will be used in the permit review process and is a matter of public record once the application is filed. Disclosure of the requested information is voluntary, but it may not be possible to evaluate the permit application or to issue a permit if the information requested is not provided.

<u>CERTIFICATION</u>: I am hereby applying for permits typically issued by the DEQ, VMRC, USACE, and/or Local Wetlands Boards for the activities I have described herein. I agree to allow the duly authorized representatives of any regulatory or advisory agency to enter upon the premises of the project site at reasonable times to inspect and photograph site conditions, both in reviewing a proposal to issue a permit and after permit issuance to determine compliance with the permit.

In addition, I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

9. APPLICANT, AGENT, PROPERTY OWNER, AND CONTRACTOR CERTIFICATIONS (Continued)							
Is/Are the Applicant(s) and Owner(s) the same? Yes No							
Legal name & title of Applicant Second applicant's legal name & title, if applicable							
Applicant's signature	Second applicant's signature						
Date	Date						
Property owner's legal name, if different from Applicant	Second property owner's legal name, if applic	cable					
Property owner's signature, if different from Applicant	Second property owner's signature						
Date	Date						
CERTIFICATION OF AUTHORIZATION TO ALLOW AGENT	S) TO ACT ON APPLICANT'S(S') BEHALF (II	F APPLICABLE)					
I (we),							
to the best of my (our) knowledge.		o trao ana accarato					
Applicant's signature	Second applicant's signature, if applicable						
Date	Date						
Agent's signature and title	Second agent's signature and title, if applicate	ble					
Date	Date						
CONTRACTOR ACKNOWLE	DGEMENT (IF APPLICABLE)						
I (we), (an APPLICANT'S LEGAL NAME(S) – complete the second by	d) lank if more than one Applicant	,					
have contractedCONTRACTOR'S NAME(S) – complete the second	(and)						
CONTRACTOR'S NAME(S) – complete the second	ond blank if more than one Contractor						
to perform the work described in this Joint Permit Application, sign	ned and dated	·					
I (we) will read and abide by all conditions as set forth in all federal, state, and local permits as required for this project. I (we) understand that failure to follow the conditions of the permits may constitute a violation of applicable federal, state, and local statutes and that we will be liable for any civil and/or criminal penalties imposed by these statutes. In addition, I (we) agree to make available a copy of any permit to any regulatory representative visiting the project site to ensure permit compliance. If I (we) fail to provide the applicable permit upon request, I (we) understand that the representative will have the option of stopping our operation until it has been determined that we have a properly signed and executed permit and are in full compliance with all of the terms and conditions.							
Contractor's name or name of firm (printed/typed)	Contractor's or firm's mailing address						
Contractor's signature and title	Contractor's license number	Date					
Applicant's signature	Second applicant's signature, if applicable						
Date	Date						



END OF GENERAL INFORMATION

The following sections are activity-specific. Fill out only the sections that apply to your particular project.

10. PRIVATE PIERS, MARGINAL WHARVES, AND UNCOVERED BOAT LIFTS

Regional Permit 17 (RP-17), authorizes the installation and/or construction of open-pile piers, mooring structures/devices, fender piles, covered boathouses/boatslips, boatlifts, osprey pilings/platforms, accessory pier structures, and certain devices associated with shellfish gardening, for private use, subject to strict compliance with all conditions and limitations further set out in the RP-17 enclosure located at http://www.nao.usace.army.mil/Missions/Regulatory/RBregional/. In addition to the information required in this JPA, prospective permittees seeking authorization under RP-17 must complete and submit the 'Regional Permit 17 Checklist' with their JPA. A copy of the 'Regional Permit 17 Checklist' is found in Appendix B of this application package. If the prospective permittee answers "yes" (or "N/A", where applicable) to all of the questions on the 'Regional Permit 17 Checklist', the permittee is in compliance with RP-17 and will not receive any other written authorization from the Corps but may not proceed with construction until they have obtained all necessary state and local permits. Note: If the prospective permittee answers "no" to any of the questions on the 'Regional Permit 17 Checklist' then their proposed structure(s) does not meet the terms and conditions of RP-17 and written authorization from the Corps is required before commencement of any work.

If the prospective permittee answers "no" to any of the questions on the 'Regional Permit 17 Checklist' then their proposed structure(s) does not meet the terms and conditions of RP-17 and written authorization from the Corps is required before commencement of any work. In those circumstances, the following information must be included in the application and/or on the drawings in order for the application to be considered complete:

- 1. The applicant MUST provide written justification/need for the encroachment if the proposed structure(s) will extend greater than one- fourth of the distance across the waterway measured from either mean high water to mean high water (including all channelward wetlands) or ordinary high water to ordinary high water (including all channelward wetlands). The measurement should be based on the narrowest distance across the waterway regardless of the orientation of the proposed structure(s).
- 2. The applicant **MUST** provide written justification/need if the proposed structure(s) is greater than five (5) feet wide or there will be less than four (4) feet elevation between the decking and the vegetated wetlands substrate.

If yes, will it be removed? ____Yes ____No

3. The Corps MAY require depth soundings across the waterway at increments designated by the Corps project manager. Inclusion of depth sounding data in the original JPA submittal is highly recommended in order to expedite permit evaluation. Depth soundings are typically taken at 10-foot increments for waterways less than 200 feet wide and 20-foot increments for waterways greater than 200 feet wide. Please include the date and time the measurements were taken, whether the data was collected at mean low water (MLW) or MHW, and how the soundings were taken (e.g., tape, range finder, etc.).

Do you have an existing pier on your property? ____Yes___ No

Is your lot platted to the mean low water shoreline? _____Yes _____No

In the spaces provided be moored	elow, give the type (e.g., sai	il, power, skiff	, etc.), size, a	nd registration number of the	he vessel(s) to be		
TYPE	LENGTH	WIE	DTH DRAFT		REGISTRATION #		
11. BOATHOUSES, GAZ	ZEBOS, COVERED BOAT	LIFTS, AND	OTHER ROC	FED STRUCTURES OVE	R WATERWAYS		
Number of vessels to be r	moored at the proposed str	ucture:		es of the structure be enclosed by the roof structure			
In the spaces provided below, give the type (e.g., sail, power, skiff, etc.), size, and registration number of the vessel(s) to be moored							
TYPE	LENGTH	WIDTH		DRAFT	REGISTRATION #		

Number of vessels to be moored

at the pier or wharf:

12. MARINAS AND COMMERCIAL, GOVERNMENTAL, AND COMMUNITY PIERS						
	rginia Department of Health's is authorization or a variance				No	
	r other hazardous materials base attach your spill continge		handled at th	e facility?Yes	No	
	ed to off-load sewage from bo			lo		
EXISTING: wet slips:	dry storage:		PROPOSEL	D: wet slips: dry s	storage:	
13 FREE STANDING M	OORING PILES, OSPREY I	NESTING P	OLES MOOF	RING BLIOYS AND DOLL	PHINS	
(not associated with		NEOTINO I	OLLO, MICOI	(IIIO DOOTS, AND DOLI	Tille	
Number of vessels to be r	moored:		Type and nu	ımber of mooring(s) propo	osed:	
In the spaces provided be moored	low, give the type (e.g., sail,	power, skiff	, etc.), size, a	nd registration number of	the vessel(s) to be	
TYPE	LENGTH	WIE	TH	DRAFT	REGISTRATION #	
Give the name and compl needed):	ete mailing address(es) of th	ne owner(s) o	of the vessel(s) if not owned by applicar	nt (attach extra sheets if	
Do you plan to reach the mooring from your own upland property?YesNo If "no," explain how you intend to access the mooring.						
44 - DOAT DAMPO						
14. BOAT RAMPS						
Will excavation be required to construct the boat ramp?YesNo. If "yes," will any of the excavation occur below the plane of the ordinary high water mark/mean high water line or in wetlands?YesNo. If "yes," you will need to fill out Section 17 for this excavation. Where will you dispose of the excavated material?						
What type of design and r gravel bedding, etc.)?	naterials will be used to cons	struct the rar	np (open pile	design with salt treated lu	mber, concrete slab on	
Location of nearest public	boat ramp		Driving dista	nce to that public ramp _	miles	
Will other structures be constructed concurrent with the boat ramp installation?YesNo If "yes," please fill out the appropriate sections of this application associated with those other activities.						

BREAKWATERS, ETC.) Information on non structural, vegetative alternatives (i.e., Living Shoreline) for shoreline stabilization is available at http://ccrm.vims.edu/coastal_zone/living_shorelines/index.html. Is any portion of the project maintenance or replacement of an existing and currently serviceable structure? _____Yes _____No If yes, give length of existing structure: _____ linear feet If your maintenance project entails replacement of a bulkhead, is it possible to construct the replacement bulkhead within 2 feet channelward of the existing bulkhead? _____Yes _____No If not, please explain below: Length of proposed structure, including returns: linear feet Average channelward encroachment of the structure from Maximum channelward encroachment of the structure from Mean high water/ordinary high water mark: _______feet Mean high water/ordinary high water mark: ______ feet ____feet Mean low water: _____feet Mean low water: ____ Maximum channelward encroachment form the back edge of the Maximum channelward encroachment from the back edge of the Beach _____feet Describe the type of construction including all materials to be used (including all fittings). Will filter cloth be used?

Yes What is the source of the backfill material? What is the composition of the backfill material? If rock is to be used, give the average volume of material to be used for every linear foot of construction: _____cubic yards What is the volume of material to be placed below the plane of ordinary high water mark/mean high water? _____cubic yards For projects involving stone: Average weight of core material (bottom layers): ______pounds per stone (Class_____
Average weight of armor material (top layers): _____pounds per stone (Class_____ Are there similar shoreline stabilization structures in the vicinity of your project site? _____Yes _____No If so, describe the type(s) and location(s) of the structure(s): If you are building a groin or jetty, will the channelward end of Has your project been reviewed by the Shoreline Erosion the structure be marked to show a hazard to navigation? Advisory Service (SEAS)? _____Yes ____No ____Yes ____No If yes, please attach a copy of their comments. 16. BEACH NOURISHMENT Source of material and composition (percentage sand, silt, clay): Volume of material: _____cubic yards Area to be covered square feet channelward of mean low water square feet channelward of mean high water square feet landward of mean low water square feet channelward of mean high water Mode of transportation of material to the project site (truck, pipeline, etc.):

15. TIDAL/NONTIDAL SHORELINE STABILIZATION STRUCTURES (INCLUDING BULKHEADS AND ASSOCIATED BACKFILL, RIPRAP REVETMENTS AND ASSOCIATED BACKFILL, MARSH TOE STABILIZATION, GROINS, JETTIES, AND

Describe the type(s) of vegetation proposed for stabilization and the proposed planting plan, including schedule, spacing, monitoring, etc. Attach additional sheets if necessary.									
17. DREDGING, MINING			LOWING TAE	BLE FOR DRE	EDGING PRO	JECTS			
			redging				ICE dredging	I	
	Hydr	raulic		l (clamshell, ne, etc.)	Hydr	raulic	Mechanical (clamshell, dragline, etc.)		
	Cubic yards	Square feet	Cubic yards	Square feet	Cubic yards	Square feet	Cubic yards	Square feet	
Vegetated wetlands									
Non-vegetated wetlands									
Subaqueous land									
Totals									
Is this a one-time dredgin (initial cycle in cu. y					ng cycles are	anticipated: _			
Composition of material (Provide documentation (i free of toxics, provide doc	.e., laboratory	results or and	alytical reports					exics. If not	
Please include a dredged material management plan that includes specifics on how the dredged material will be handled and retained to prevent its entry into surface waters or wetlands. If on-site dewatering is proposed, please include plan view and cross-sectional drawings of the dewatering area and associated outfall.									
Will the dredged material If yes, please explain:	be used for a	ny commercia	al purpose or	beneficial use	?Yes	No			
If this is a maintenance d Permit number of original							e original perr	 nit.)	

16. BEACH NOURISHMENT (Continued)

For mining projects: On separate sheets of paper, explain the operation (i.e., April through September), and volume (i.e., April through September), and volume (i.e., April through September).	
duration (i.e., April through September), and volume (in cubic yard handling methods of mined material, including the dimensions of t material and the need (or no need) for a liner or impermeable mat ground water; 3) how equipment will access the mine site; and 4) segments that are currently on the effective Section 303(d) Total that could be a segment of the country of the coun	the containment berm used for upland disposal of dredged terial to prevent the leaching of any identified contaminants into) verification that dredging: a) will not occur in water body
x) or that have an approved TMDL; b) will not exacerbate any imp allocation/limit/conditions imposed by an approved TMDL (see, "W	pairment; and c) will be consistent with any waste load
Have you applied for a permit from the Virginia Department of Min Existing permit number: Date permit is	nes, Minerals and Energy?YesNo If Yes: ssued:
Contributing drainage area:square miles	Average stream flow at site (flow rate under normal rainfall conditions):cfs
18. FILL (not associated with backfilled shoreline structures) boathouses) IN WETLANDS OR WATERS, OR ON DUNES/BE	
Source and composition of fill material (percentage sand, silt, clay	/, rock):
Provide documentation (i.e., laboratory results or analytical report free of toxics, provide documentation of proper disposal (i.e., bill of Documentation is not necessary for fill material obtained from on-	of lading from commercial supplier or disposal site). site areas.
Explain the purpose of the filling activity and the type of structure	to be constructed over the filled area (if any):
Describe any structure that will be placed in wetlands/waters or or	n a beach dune and its purpose:
Will the structure be placed on pilings? Yes No	Total area occupied by any structure Square Feet
How far will the structure be placed channelward from the back edge of the dune?feet	How far will the structure be placed channelward from the back edge of the beach?feet
19. NONTIDAL STREAM CHANNEL MODIFICATIONS FOR REPERMANENT RELOCATIONS	STORATION OR ENHANCMENT, or TEMPORARY OR
If proposed activities are being conducted for the purposes of comproviding all information required by the most recent version of the District of the U.S. Army Corps of Engineers and the Virginia Department of the U.S. Required information outlined by the methodolo	

ENHANCMENT, or TEMPORARY OR PERMANENT REL	AL STREAM CHANNEL MODIFICATIONS FOR RESTORATION OR OCATIONS (Continued) 19. NONTIDAL STREAM CHANNEL NT, or TEMPORARY OR PERMANENT RELOCATIONS (Continued)
Existing average stream flow at site (flow rate under normal rainfall conditions):cfs	Proposed average stream flow at site after modifications (flow rate under normal rainfall conditions):cfs
Explain, in detail, the method to be used to stabilize the bar	nks:
Explain the composition of the existing stream bed (percent	t cobble, rock, sand, etc.):
Will low-flow channels be maintained in the modified stream Describe how:	n channel?YesNo.
Will any structure(s) be placed in the stream to create riffles If yes, please explain:	s, pools, meanders, etc.?YesNo
20. UTILITY CROSSINGS	
Type of crossing:overheadtrencheddir	rectionally-drilled
Method of clearing corridor of vegetation (check all that app cutting vegetation above the soil surface	oly): mechanized land clearing that disturbs the soil surface
	utility line (including gravel bedding for trenched installations, bentonite of events to detail how the installation will be accomplished (including
No.	itional utilities that may propose to co-locate at a later date?Yes
For overhead crossings over navigable waterways (including crossings or bridges over the waterway relative to mean high	ng all tidal waterways), please indicate the height of other overhead gh water, mean low water, or ordinary high water mark:
Nominal system voltage, if project involves power lines:	
Total number of electrical circuits:	

19. NONTIDAL STREAM CHANNEL MODIFICATIONS FOR RESTORATION OR ENHANCMENT, or TEMPORARY OR

20. UTILITY CROSSINGS (Continued)	
Will there be an excess of excavated material?Yes If so, describe the method that will be undertaken to dispose of, at give that location:	
Will any excess material be stockpiled in wetlands?Yes _ If so, will the stockpiled material be placed on filter fabric or some	
Will permanent access roads be placed through wetlands/streams If yes, will the roads be (check one) \square at grade \square above grade	
Will the utility line through wetlands/waters be continually maintain If maintained, what is the maximum width?feet	
21. ROAD CROSSINGS	
Have you conducted hydraulic studies to verify the adequacy of the If so, please attach a copy of the hydraulic study/report. Virginia Department of Transportation (VDOT) standards require to road, culvert, and bridge projects within FEMA-designated floodplate requires pipes and culverts 24 inches or less in diameter to be contained pipes and culverts greater than 24 inches to be countersunk at Hydraulic capacity is determined based on the reduced capacity of	that the backwater for a 100 year storm not exceed 1 foot for all ains. Virginia Department of Environmental Quality (DEQ) untersunk three inches below the natural stream bed elevations, at least six inches below the natural stream bed elevations.
Will the culverts be countersunk below the stream bottom?	YesNo. If no, explain:
If the project entails a bridged crossing and there are similar cross water, mean low water, or ordinary high water mark of those similar For all bridges proposed over navigable waterways (including all to Guard to determine if a permit is required of their agency.	ar structures?feet above
On separate sheets of paper, describe the materials to be used, the sequence of construction events, and if bedrock conditions may be culvert crossings including wing walls or rip rap.	
22. IMPOUNDMENTS, DAMS, AND STORMWATER MANAGEM If the impoundment or dam is a component of a water withdra	
Will the proposed impoundment, dam, or stormwater managemen a farm)? For DEQ permitting purposes, a farm is considered to be Yes No	t facility be used for agricultural purposes (e.g., in the operation of e a property or operation that produces goods for market.
What type of materials will be used in the construction (earth, con-	crete, rock, etc.)?
What is the source of these materials?	
Provide the dimensions of proposed impoundment, dam, or storm structures.	water management facility, including the height and width of all
Storage capacity* of impoundment:acre-feet *should be given for the normal pool of recreational or farm ponds, or design pool for stormwater management ponds or reservoirs (the elevation the pond will be at for the design storm, e.g., 10-year, 24-hour storm)	Surface area** of impoundment:acres **should be given for the normal pool of recreational or farm ponds, or design pool for stormwater management ponds or reservoirs (the elevation the pond will be at for the design storm, e.g., 10-year, 24-hour storm)

22. IMPOUNDMENTS, DAMS, AND STORMWATER MANAGEMENT FACILITIES (Continued)
Is the proposed project excluded from the Virginia Dam Safety Regulations? Yes No Uncertain
If not excluded, does your proposed project comply with the Virginia Dam Safety Regulations? Yes No Uncertain
Does the proposed design include a vegetation management area per §10.1-609.2? Yes No Uncertain If your answer to these questions is no or uncertain, you should contact the Virginia Department of Conservation and Recreation's Dam Safety Program at (804) 371-6095, or reference the regulations on the Web at http://www.dcr.virginia.gov/dam_safety_and_floodplains/index.shtml
For stormwater management and flood control facilities:
Design storm event:year storm Retention time:hours
Current average flow (flow rate under normal rainfall conditions):cfs
Method used to derive average flow:
Proposed peak outflow for the design storm provided above:cfs
Has the facility been designed as an Enhanced Extended Detention Basin or an Extended Detention Basin in accordance with the Minimum Standard 3.07 of the Virginia Stormwater Management Handbook, Volume I (published by the Virginia Department of Conservation and Recreation, 1999), or in accordance with the latest version of this handbook?No
Will the impoundment structure be designed to pass a minimum flow at all times?YesNo
If so, please give the minimum rate of flow:cfs
What is the drainage area upstream of the proposed impoundment?square miles
How much of your proposed impoundment structure will be located on the stream bed?square feet
What is the area of vegetated wetlands that will be excavated and/or back-flooded by the impoundment?square feet
What is the area and length of streambed that will be excavated and/or back-flooded by the impoundment? square feet linear feet
Are fish ladders being proposed to accommodate the passage of fish?YesNo
23. OUTFALLS NOT ASSOCIATED WITH PROPOSED WATER WITHDRAWAL ACTIVITIES
Type and size of pipe(s):
Daily rate of discharge:mgd
If the discharge will be thermally-altered, provide the maximum temperature:
Contributing drainage area:square miles Average daily stream flow at site:cfs
Have you received a Virginia Discharge Elimination System (VPDES) permit for the proposed project? Yes No.
If yes, please provide the VPDES permit number:
If no, is there a permit action pending? Yes No. If pending, what is the facility name?

The following sections are typically related to surface water withdrawal activities; Federal Energy Regulatory Commission license projects; or impacts likely to require instream flow limits. Examples of such projects include, but are not limited to, reservoirs, irrigation projects, power generation facilities, and public water supply facilities that may or may not have associated features, such as dams, intake pipes, outfall structures, berms, etc.

If completing these sections, enter "N/A" in any section that does not apply to the project.

24. INTAKES, OUTFALLS, AN ACTIVITIES)	D WATER CONTROL STR	UCTU	RES (INCLUDING ALL PROPOS	ED WATER WITHDRAWAL
For intakes:			For outfalls:	
Type and size of pipe(s):		-	Type, size, and hydraulic ca	apacity (under normal
Type and size of pump(s): _			conditions) of pipe(s):	,, and
Average and Maximum daily	rate of withdrawal:			
and mgd			Daily rate of discharge:	mgd
Velocity of withdrawal:		fps	If the discharge will be therr	mally-altered, provide the
Screen mesh size:	inches /	mm	maximum temperature:	
If other sizing units, ple	ase specify:		Contributing drainage area	• ,
O			square m	
Contributing drainage area a			under normal rainfall condition	at discharge point(s) (flow rate ions): cfs
Average daily stream flow at withdrawal point(s) (flow rate		ate	Method(s) used to derive av	
under normal rainfall condition				
Method(s) used to derive av	·			
			Latitude and longitude of dis	scharge point(s) (degrees.
			-	
Average annual stream flow	at withdrawal point(s):		, ,	
cfs	1 (/			
Latitude and longitude of withdrawal point(s) (degrees,				
minutes, seconds):				
·				
intake or dam site (not at the stre intake or dam site based upon th United States Geologic Survey (eam gage; if there is not a g ne most closely related wate USGS)). Median flow is the an is also sometimes referre	age at ershed value ed to a	monthly stream flows in cubic feet the intake or dam site, you will no in which there is an operational st at which half of the measurement s the '50% exceedence flow'. The in (average) flow.	eed to interpolate flows to the tream gage monitored by the ts are above and half of the
Month	Median flow (cfs)		Month	Median flow (cfs)
January			July	
February			August	
March			September	
April			October	
May			November	
June			December	

24. INTAKES, OUTFALLS, AND WATER CONTROL STRUCTURES (Continued)
Describe the stream flow gages used, USGS stream flow gage site number and site name (e.g., USGS 01671100 Little River near Doswell, VA), the type of calculations used (such as drainage area correction factors), and the period of record that was used to calculate the median flows provided in the table above. Generally, the period of record should span a minimum of 30 years.
For interbasin transfer of water resources proposed from either the Chowan River, New River, Potomac River, Roanoke River, Big Sandy River, or Tennessee River basins to another river basin, provide the following information:
Destination location (discharge point) of the transfer: 8-digit USGS Hydrologic Unit Code (HUC) (See http://cfpub.epa.gov/surf/locate/index.cfm): If known, indicate the 10-digit and 12-digit USGS HUCs (see http://consapps.dcr.virginia.gov/htdocs/maps/HUExplorer.htm):
Latitude and Longitude:
Provide any available historical low-flows at the intake or dam site.
Describe how the proposed withdrawal at the intake or dam site will impact stream flows in terms of rates, volumes, frequency, etc. (e.g., percent of the flow to be withdrawn, percent of withdrawal returned to the original source, etc.).
Describe how the withdrawal of water will vary over time. For example, will the withdrawal vary by the time of year, by the time of day, or by the time of week? Examples of projects that should describe variable withdrawals include, but are not limited to: power plant cooling withdrawals that increase and decrease seasonally; golf course irrigation; municipal water supply; nurseries; ski
resorts that use water for snowmaking; and resorts with weekend or seasonal variations.

Provide the amount of water that will be lost due to consumptive use. For the purpose of this application, consumptive use means the withdrawal of surface waters without recycling of said waters to their source or basin of origin. Examples of consumptive uses are water that is evaporated in cooling towers or by other means in power plants; irrigation water (all types); residential water use that takes place outside of the home; and residential water use both inside and outside of homes for residences served by septic systems. Projects that propose a transfer of water from one river basin to another and/or localities that sell water to other jurisdictions, should document the portion of the withdrawal that is not returned to the originating watershed. Proposed monthly consumptive volume (million gallons): Attach a map showing the <i>location</i> of the withdrawal and of the return of flow, and provide the <i>amount</i> of the return flow (million gallons). For withdrawals proposed on an impoundment, provide a description of flow or release control structures. Include type of structure,
rate of flow, size, capacity, invert elevation of outfall pipes referenced to the normal pool elevation, and the mechanism used to control release. Provide a description of available water storage facilities. Include the volume, depth, normal pool elevation, unusable storage volume and dimensions. If applicable, stage-storage relationship at the impounding structure (the volume of water in the impoundment at varying stages of water depth) and volume or rate of withdrawals from the storage facility.
25. WATER WITHDRAWAL USE(S), NEED, AND ALTERNATIVES (Attach additional sheets if needed.)
Describe the proposed use(s) and need for the surface water and information on how demand for surface water was determined. Golf courses must provide documentation to justify the amount of water withdrawal, such as the amount of acreage under irrigation, the acreage of fairways versus greens, type of turf grass, evapotranspiration, and irrigation efficiency. Agricultural users must supply documentation justifying their requested withdrawal amount, such as type of crop, livestock, or other agriculture animal, number of animals, watering needs, acres irrigated, inches of water applied, and frequency of application. Other users of withdrawals for purposes other than those described above must provide sufficient documentation to justify the requested withdrawal amounts.

25. WATER WITHDRAWAL USE(S), NEED, AND ALTERNAT Provide the following information at the water intake or dam site. gallons per minute, cubic feet per second, etc.).	IVES (Continued) . Specify the units of measurement (e.g., million gallons per day,
Proposed maximum instantaneous withdrawal	
Proposed average daily withdrawal	
Proposed maximum daily withdrawal	
Proposed maximum monthly withdrawal	
Proposed maximum annual withdrawal	
Describe how the above withdrawals were calculated, including documentation or resources used to support the calculations, su use, new uses, changes to service areas, and if applicable, evaporation of the control of the control of the calculations of the calculation	ch as population projections, population growth rates, per-capita
For surface water withdrawals, public water supply withdrawals, establish the local water supply need. Attach additional sheets i	
EXISTING	PROJECTED
Existing supply sources, yields, and demands:	Projected demands over a minimum 30-year planning period:
Peak day withdrawal:	Projected demands in local or regional water supply plan (9VAC25-780 et seq.) or demand for the project service area, if that is smaller in area:
Safe yield: Lowest daily flow of record:	Statistical population (growth) trends:
Types of water uses (residential, public water supply, commercial, industrial, agricultural):	Projected demands by type of water use:
Existing water conservation measures and drought response plan, including what conditions trigger implementation:	Projected demands without water conservation measures:
	Projected demands with long-term water conservation measures:
For surface water withdrawals other than public water supply, pr sources of water are available for the proposed project during tire	

25. WATER WITHDRAWAL USE(S), NEED, AND ALTERNATIVES (Continued)
Provide information from the State Water Resources Plan (http://www.deq.virginia.gov/Programs/Water/WaterSupplyWaterQuantity/WaterSupplyPlanning/StateWaterResourcesPlan.aspx) and the local or regional water supply plan that covers the area in which the proposed water withdrawal project is located (http://www.deq.virginia.gov/Portals/0/DEQ/Water/WaterSupplyPlanning/SWRP%20Final/App%20A%20Water%20Supply%20Plans %20and%20Participating%20Localities.pdf). Include information from the plan that pertains to projected demand, analysis of alternatives, and water conservation measures. Discuss any discrepancies between the water supply plan and the proposed project. For projects that propose a transfer of water resources from the Chowan River, New River, Potomac River, Roanoke River, Big Sandy River, or Tennessee River basins to another river basin, information should be provided from the water supply plans for both the source and receiving basins. Attach additional sheets if needed.
Provide an alternatives analysis for the proposed water withdrawal project, including the required range of alternatives to be analyzed; a narrative outlining the opportunities and status of regional efforts undertaken; and the criteria used to evaluate each alternative. The analysis must address all of the criteria contained in 9VAC25-360.
Describe any existing, flow-dependent beneficial uses along the affected stream reach. Include both instream and offstream uses. Describe the stream flow necessary to protect existing beneficial uses, how the proposed withdrawal will impact existing beneficial uses, and any measures proposed to mitigate any adverse impacts that may arise. For projects that propose a transfer of water resources from the Chowan River, New River, Potomac River, Roanoke River, Big Sandy River, or Tennessee River basins to another river basin, this analysis should include both the source and receiving basins. For the purposes of this application, beneficial instream uses include, but are not limited to, the protection of fish and wildlife habitat; maintenance of waste assimilation; recreation; navigation; and cultural and aesthetic values. Offstream beneficial uses include, but are not limited to, domestic uses (including public water supply); agricultural uses; electric power generation; commercial uses; and industrial uses.
Describe the aquatic life known to be present along the affected stream reach. Describe aquatic life that may be impacted by the proposed water withdrawal. Include the species' habitat requirements. For projects that propose a transfer of water resources from either the Chowan River, New River, Potomac River, Roanoke River, Big Sandy River, or Tennessee River basins to another river basin, this analysis should include both the source and receiving basins.

26. PUBLIC COMMENTS/ISSUES FOR MAJOR WATER WITHDRAWALS OR INTERBASIN TRANSFERS

For new or expanded surface water supply projects, use separate sheets of paper to summarize the steps taken to seek public input per 9VAC25-210-320, and identify the issues raised during the public information process.

For transfer of water resources proposed from either the Chowan River, New River, Potomac River, Roanoke River, Big Sandy River, or Tennessee River basins to another river basin, if public input was not required per 9VAC25-210-320, summarize on separate sheets of paper any coordination and/or notice provided to the public, local/state government, and interested parties in the affected river basins and identify any issues raised.

APPENDIX A

Adjacent Property Owner's Acknowledgement Form

I,	, own land next to/ across the water from/ in the same cover
(print adjacent property owner's name)	, own land next to/ across the water from/ in the same cove
as the land of(print applicant's name)	
(print applicant's name)	
I have reviewed the applicant's project drawings dated	to be submitted for all
(date of drawings)
necessary federal, state, and local permits.	
I have no comment regarding the proposal	
I do not object to the proposal	
I object to the proposal	
The applicant has agreed to contact me for additional comme	ents if the proposal changes prior to construction of the project
(Before signing this form, please be sure that you have checked t	he appropriate option above)
Adjacent property owner's signature	
Aujacent property owner a signature	
Data	

NOTE: IF YOU OBJECT TO THE PROPOSAL, THE REASON(S) YOU OPPOSE THE PROJECT MUST BE SUBMITTED TO VMRC IN WRITING. AN OBJECTION WILL NOT NECESSARILY RESULT IN A DENIAL OF A PERMIT FOR THE PROPOSED WORK. HOWEVER, VALID COMPLAINTS WILL BE GIVEN FULL CONSIDERATION DURING THE PERMIT REVIEW PROCESS.

APPENDIX A

Adjacent Property Owner's Acknowledgement Form

I,	, own land next to/ across the water from/ in the same cove
(print adjacent property owner's name)	
as the land of(print applicant's name)	·
(print applicant's name)	
I have reviewed the applicant's project drawings dated(da	ate of drawings) to be submitted for all
necessary federal, state, and local permits.	
I have no comment regarding the proposal	
I do not object to the proposal	
I object to the proposal	
The applicant has agreed to contact me for additional comme	nts if the proposal changes prior to construction of the project.
(Before signing this form, please be sure that you have checked th	e appropriate option above)
Adjacent property owner's signature	
Date	

NOTE: IF YOU OBJECT TO THE PROPOSAL, THE REASON(S) YOU OPPOSE THE PROJECT MUST BE SUBMITTED TO VMRC IN WRITING. AN OBJECTION WILL NOT NECESSARILY RESULT IN A DENIAL OF A PERMIT FOR THE PROPOSED WORK. HOWEVER, VALID COMPLAINTS WILL BE GIVEN FULL CONSIDERATION DURING THE PERMIT REVIEW PROCESS.



REGIONAL PERMIT 17 CHECKLIST

Expires: September 5, 2023

Please review the 18-RP-17 enclosure before completing this form and note 18-RP-17 can only be used for proposed <u>PRIVATE USE</u> structure(s) that comply with the terms and conditions of 18-RP-17. Copies can be obtained online at http://www.nao.usace.army.mil/Missions/Regulatory/RBregional/.

YES	NO		(1) Has the permittee reviewed the 18-RP-17 enclosure and verified that the proposed structure(s) is in compliance with all the terms, conditions, and limitations of 18-RP-17?
YES	NO		(2) Does the proposed structure(s) extend no more than one-fourth of the distance across the waterway measured from either mean high water (MHW) to MHW (including all channelward wetlands) or ordinary high water (OHW) to OHW (including all channelward wetlands)?
YES	NO		(3) Does the proposed structure(s) extend no more than 300 feet from MHW or OHW (including all channelward wetlands)?
YES	NO	N/A	(4) Does the proposed structure(s) attach to the upland at a point landward of MHW or OHW (including all channelward wetlands)?
YES	NO	N/A	(5) If the proposed structure(s) crosses wetland vegetation, is it an open-pile design that has a <u>maximum</u> width of five (5) feet and a <u>minimum</u> height of four (4) feet between the decking and the wetland substrate?
YES	NO	N/A	(6) Does the proposed structure(s) include no more than two (2) boatlifts and no more than two (2) boat slips?
YES	NO	N/A	(7) Is the open-sided roof structure designed to shelter a boat \leq 700 square feet and/or is the open sided roof structure or gazebo structure designed to shelter a pier \leq 400 square feet?
YES	NO	N/A	(8) Are all piles associated with the proposed structure(s) non-steel, less than or equal to 12" in diameter, and will less than or equal to 25 piles be installed channelward of MHW?
YES	NO	N/A	(9) Is all work occurring behind cofferdams, turbidity curtains, or other methods to control turbidity being utilized when operationally feasible and federally listed threatened or endangered species may be present?
YES	NO	N/A	(10) If the proposed structure(s) is to be located within an anadromous fish use area, the prospective permittee will adhere to the anadromous fish use area time of year restriction (TOYR) prohibiting in-water work from occurring between February 15 through June 30 of any given year if (1) piles are to be installed with a cushioned impact hammer and there is less than 492 feet between the most channelward pile and mean low water (MLW) on the opposite shoreline or (2) piles are to be installed with a vibratory hammer and there is less than 384 feet between the most channelward pile and MLW on the opposite shoreline.
YES	NO		(11) Is all work occurring outside of submerged aquatic vegetation (SAV) mapped by the Virginia Institute of Marine Sciences' (VIMS) most recent survey year and 5 year composite?
YES	NO		(12) Has the permittee ensured the construction and/or installation of the proposed structure(s) will not affect federally listed threatened or endangered species or designated critical habitat?
YES	NO		(13) Will the proposed structure be located outside of Broad Creek in Middlesex County, Fisherman's Cove in Norfolk, or the Salt Ponds in Hampton?
YES	NO		(14) Will the proposed structure(s) be located outside of the waterways containing a Federal Navigation Project listed in Permit Specific Condition 12 of 18-RP-17 and/or will all portions of the proposed structure(s) be located more than 85 feet from the Federal Navigation Project?

YES	NO		(15) Will the proposed structure(s) be located outside a USACE Navigation and Flood Risk Management project area?
YES	NO		(16) Will the proposed structure(s) be located outside of any Designated Trout Waters?
YES	NO	N/A	(17) If the proposed structure(s) includes flotation units, will the units be made of materials that will not become waterlogged or sink if punctured?
YES	NO	N/A	(18) If the proposed structure(s) includes flotation units, will the floating sections be braced so they will not rest on the bottom during periods of low water?
YES	NO		(19) Is the proposed structure(s) made of suitable materials and practical design so as to reasonably ensure a safe and sound structure?
YES	NO		(20) Will the proposed structure(s) be located on the property in accordance with the local zoning requirements?
YES	NO	N/A	(21) If the proposed structure(s) includes a device used for shellfish gardening, will the device be attached directly to a pier and limited to a total of 160 square feet?
YES	NO	N/A	(22) If the proposed structure(s) includes a device used for shellfish gardening, does the permittee recognize this RP does not negate their responsibility to obtain an oyster gardening permit (General Permit #3) from Virginia Marina Resources Commission's Habitat Management Division?
YES	NO		(23) Does the permittee recognize this RP does not authorize any dredging or filling of waters of the United States (including wetlands) and does not imply that future dredging proposals will be approved by the Corps?
YES	NO		(24) Does the permittee understand that by accepting 18-RP-17, the permittee accepts all of the terms and conditions of the permit, including the limits of Federal liability contained in the 18-RP-17 enclosure? Does the permittee acknowledge that the structures permitted under 18-RP-17 may be exposed to waves caused by passing vessels and that the permittee is solely responsible for the integrity of the structures permitted under 18-RP-17 and the exposure of such structures and vessels moored to such structures to damage from waves? Does the permittee accept that the United States is not liable in any way for such damage and that it shall not seek to involve the United States in any actions or claims regarding such damage?

IF YOU HAVE ANSWERED "NO" TO ANY OF THE QUESTIONS ABOVE, REGIONAL PERMIT 17 (18-RP-17) DOES NOT APPLY AND YOU ARE REQUIRED TO OBTAIN WRITTEN AUTHORIZATION FROM THE CORPS PRIOR TO PERFORMING THE WORK.

IF YOU HAVE ANSWERED "YES" (OR "N/A", WHERE APPLICABLE) TO ALL OF THE QUESTIONS ABOVE, YOU ARE IN COMPLIANCE WITH REGIONAL PERMIT 17 (18-RP-17). PLEASE SIGN BELOW, ATTACH, AND SUBMIT THIS CHECKLIST WITH YOUR COMPLETED JOINT PERMIT APPLICATION (JPA). THIS SIGNED CERTIFICATE SERVES AS YOUR LETTER OF AUTHORIZATION FROM THE CORPS. YOU WILL NOT RECEIVE ANY OTHER WRITTEN AUTHORIZATION FROM THE CORPS; HOWEVER, YOU MAY NOT PROCEED WITH CONSTRUCTION UNTIL YOU HAVE OBTAINED ALL OTHER NECESSARY STATE AND LOCAL PERMITS.

I CERTIFY THAT I HAVE READ AND UNDERSTAND ALL CONDITIONS OF THE REGIONAL PERMIT 17 (18-RP-17), DATED SEPTEMBER 2018, ISSUED BY THE US ARMY CORPS OF ENGINEERS, NORFOLK DISTRICT REGULATORY BRANCH (CENAO-WRR), NORFOLK, VIRGINIA.

	Proposed work to be located at:
Signature of Property Owner(s) or Agent	
Date	VMRC Number:

APPENDIX C

Chesapeake Bay Preservation Act Information

Please answer the following questions to determine if your project is subject to the requirements of the Bay Act Regulations:

1. Is your project located within Tidewater Virginia? ____Yes ____No (See map on page 31) - If the answer is "no", the Bay Act requirements do not apply; if "yes", then please continue to question #2.

2. Please indicate if the project proposes to impact any of the following Resource Protection Area (RPA) features: ____ Tidal wetlands, ____ Nontidal wetlands connected by surface flow and contiguous to tidal wetlands or water bodies with perennial flow, ____ Tidal shores, ____ Other lands considered by the local government to meet the provisions of subsection A of 9VAC25-830-80 and to be necessary to protect the quality of state waters (contact the local government for specific information),

If the answer to question #1 was "yes" and any of the features listed under question #2 will be impacted, compliance with the Chesapeake Bay Preservation Area Designation and Management Regulations is required. The Chesapeake Bay Preservation Area Designation and Management Regulations are enforced through locally adopted ordinances based on the Chesapeake Bay Preservation Act (CBPA) program. Compliance with state and local CBPA requirements mandates the submission of a *Water Quality Impact Assessment (WQIA)* for the review and approval of the local government. Contact the appropriate local government office to determine if a WQIA is required for the proposed activity(ies).

A buffer area not less than 100 feet in width located adjacent to and landward of the components listed above, and along

The individual localities, <u>not</u> the DEQ, USACE, or the Local Wetlands Boards, are responsible for enforcing the CBPA requirements and, therefore, local permits for land disturbance are not issued through this JPA process. **Approval of this wetlands permit does not constitute compliance with the CBPA regulations nor does it guarantee that the local government will grant approval for encroachments into the RPA that may result from this project.**

Notes for all projects in RPAs

Development, redevelopment, construction, land disturbance, or placement of fill within the RPA features listed above requires the approval of the locality and may require an exception or variance from the local Bay Act ordinance. Please contact the appropriate local government to determine the types of development or land uses that are permitted within RPAs.

Pursuant to 9VAC25-830-110, on-site delineation of the RPA is required for all projects in CBPAs. Because USGS maps are not always indicative of actual "in-field" conditions, they may not be used to determine the site-specific boundaries of the RPA.

Notes for shoreline erosion control projects in RPAs

Re-establishment of woody vegetation in the buffer will be required by the locality to mitigate for the removal or disturbance of buffer vegetation associated with your proposed project. Please contact the local government to determine the mitigation requirements for impacts to the 100-foot RPA buffer.

Pursuant to 9VAC25-830-140 5 a (4) of the Virginia Administrative Code, shoreline erosion projects are a permitted modification to RPAs provided that the project is based on the "best technical advice" and complies with applicable permit conditions. In accordance with 9VAC25-830-140 1 of the Virginia Administrative Code, the locality will use the information provided in this Appendix, in the project drawings, in this permit application, and as required by the locality, to make a determination that:

- 1. Any proposed shoreline erosion control measure is necessary and consistent with the nature of the erosion occurring on the site, and the measures have employed the "best available technical advice"
- 2. Indigenous vegetation will be preserved to the maximum extent practicable
- 3. Proposed land disturbance has been minimized
- 4. Appropriate mitigation plantings will provide the required water quality functions of the buffer (9VAC25-830-140 3)
- 5. The project is consistent with the locality's comprehensive plan

both sides of any water body with perennial flow.

6. Access to the project will be provided with the minimum disturbance necessary.



APPENDIX D

Sample Drawings

On the following pages, you will find lists of information required on drawings, as well as sample drawings in plan and cross-sectional views. While the lists attempt to capture all required information for drawings, please verify your submittal with the applicable agency regulations. For DEQ drawing definitions and requirements, see Sections 10 and 80 of 9VAC25-210; and in Section 60 of the general permit regulations 9VAC25-660, 9VAC25-670, 9VAC25-680, and 9VAC25-690. Please be advised that some Local Wetlands Boards (LWB) require you to have a licensed engineer certify the drawings. You should contact your LWB to determine their specific requirements. Failure to include all necessary information on your drawings may mean that your application is not considered complete by one or more agencies.

All projects will require the submittal of plan view and cross-sectional view drawings. Drawings should be drawn to a scale no smaller than 1 inch = 200 feet. The number of sets of drawings to be submitted is detailed in the HOW TO APPLY section starting on page 2 of this package. Drawings can be computer-generated or hand-drawn. The sample drawings demonstrate the **general** format necessary, but for ease of viewing, not all of the required information is shown in the sample drawings.

Plan view drawings should contain the following general informational items:

- Name of project
- North arrow
- ❖ Scale
- Waterway name, if designated
- Existing topographic or bathymetric contours
- Proposed topographic or bathymetric contours
- Width of waterway from the mean high water level to the mean high water level (tidal areas), or the ordinary high water mark to the ordinary high water mark (nontidal areas)
- Direction of flood and ebb (tidal areas), and/or direction of flow in nontidal areas (if applicable)
- Mean low water level and mean high water level (tidal areas), or ordinary high water mark (nontidal areas)
- Landward limit of the dune or beach at the site
- Limits of proposed impacts to surface waters, such as fill areas, riprap scour protection placement, and dredged areas; the amount of such impacts in square feet and acres; and the latitude/longitude (decimal degrees) at each impact site
- All delineated wetlands and all surface waters on the site, including the Cowardin classification (i.e., emergent, scrub-shrub, or forested) for those surface waters and waterway name, if designated

AND Plan view drawings should also contain the following specific informational items if they apply to the project:

Resource Impact/Protection-Specific Items:

- Limits of: existing, non-delineated wetlands, open water, or streams, including submerged aquatic vegetation (SAV), riffle/pool complexes, or bars; Chesapeake Bay Preservation Act Resource Protection Area(s) (RPA), including the 100-foot buffer; proposed clearing within the RPA buffer; and any areas that are under a deed restriction, conservation easement, restrictive covenant, or other land use protective instrument (i.e., protected areas)
- Location and type of existing vegetation within the 100-foot RPA buffer and location of proposed wetland planting areas (as restoration for temporary impacts or mitigation for permanent impacts)
- Historic/cultural resources
- Threatened/Endangered resources

Structure/Project-Specific Items:

- Existing and proposed structures, labeled as 'existing' and 'proposed', and their dimensions. These items may include pier(s), including L-heads, T-heads, platforms, and/or decks; roof(s) on roofed structures located over waterways, including boathouses; gasoline storage tanks and/or structures for collecting and handling hazardous material, including settling tanks for travel lift washdown water, paint chips, etc.; return walls; tie-ins to existing bulkhead(s) or riprap; utility line easement(s); utility line/road right(s)-of-way; aerial transmission line structure(s), including towers, poles, platforms, etc.; onsite or offsite dredged material disposal areas, including location of all berms, spillways, erosion and sediment control measures, outfall pipes, and aprons; temporary stockpiles of excavated material; temporary construction access facilities; risers and/or emergency spillways, labeled with their proposed invert elevations; design pool/normal pool for stormwater management ponds/impoundments/reservoirs; intakes and/or outfalls, including splash aprons, relative to mean high water, mean low water, or ordinary high water mark(s); anchoring devices and weights (mooring buoys), including the total swing radius
- Channelward encroachment of proposed structure(s) from mean high water and mean low water, or from ordinary high water mark
- For piers that cover ¼ or more of the waterway width: depth soundings, taken at the mean low water level (tidal areas) or the ordinary high water mark (nontidal areas)
- Distance(s) between structure(s) (piers, boathouses, catwalks, etc.) and mooring pile(s)
- Minimum distance between dredge cut and vegetated wetlands
- Latitude and longitude of all mooring structures, in degrees, minutes, and seconds
- End points and turning points along proposed bulkhead(s), labeled as such

APPENDIX D (continued)

- For bulkheads, measurements from each end point and each turning point along proposed bulkhead(s) to two fixed points of reference (labeled as such)
- Structure or method used to contain fill (hay bales, silt fences, etc.)
- Dimensions of impoundment, dam, or stormwater management facility and area of any vegetative management areas

Cross-sectional view drawings, and when required profile view* drawings, should contain the following General Informational items:

- Name of project
- North arrow
- ❖ Scale
- Waterway name
- Mean low water and mean high water lines (tidal areas), and/or ordinary high water mark (nontidal areas)
- Direction of flood and ebb (tidal areas), and/or direction of flow in nontidal areas (if applicable)
- Existing contours of the bottom (depths relative to mean low water or ordinary high water mark) and the bank itself
- Existing contours of the dune or beach
- Existing and proposed elevations
- Location of all existing and proposed structures
- Limits of proposed impacts to surface waters, such as fill areas, riprap scour protection placement, and dredged areas; the amount of such impacts in square feet and acres; and the latitude/longitude (decimal degrees) at each impact site


AND Cross-sectional view drawings, and when required profile view* drawings, should also contain the following specific informational items if they apply to the project:


Resource impact/protection-specific Items:

- Limits of: existing, non-delineated wetlands, open water, or streams, including submerged aquatic vegetation (SAV), riffle/pool complexes, or bars; Chesapeake Bay Preservation Act Resource Protection Area(s) (RPA), including the 100-foot buffer; and proposed clearing within the RPA buffer
- Riprap scour protection
- Proposed wetland planting areas, relative to mean high water and mean low water (tidal areas), or ordinary high water mark (nontidal areas)
- Depth of buried toe of riprap or marsh toe stabilization
- Base width, top width, and slope of stone/concrete stabilization structures


Structure/Project-Specific Items:


- Existing and proposed structures, labeled as 'existing' and 'proposed', and their dimensions. These items may include fill areas, labeled with square footage(s) or acreage(s) over vegetated wetlands and subaqueous bottom; berms, spillways, erosion and sediment control measures, outfall pipes, and aprons at onsite or offsite dredged material disposal area(s); bank grades; deadmen, sheeting, knee braces, etc., as used in the construction of bulkheads; filter cloth; weep holes; intakes and/or outfalls, including splash aprons, relative to mean high water, mean low water, or ordinary high water mark; risers and/or emergency spillways; low-flow channels; culverts, including their proposed invert elevations and diameters; anchoring systems for aquaculture structures; type of chain used to secure mooring buoys to subaqueous bottom
- For dredge projects, proposed contours of the bottom (depth relative to mean low water or ordinary water level)
- ❖ Bottom width of proposed dredge cut, projected side slope of cut, and estimated top width of cut
- Ponding depth of onsite or offsite dredged material disposal area
- Minimum distance between pier decking and vegetated wetland substrate (a.k.a. the "mud line")
- Water depth below mean low water at the end of proposed boat ramps.
- Depth of penetration of pilings and/or sheeting (bulkheads)
- Elevation of any proposed fill (including backfill)
- Structure or method used to contain fill (hay bales, silt fences, etc.)
- Design pool/normal pool elevation for stormwater management facilities/impoundments/reservoirs
- Vertical distance from the water surface (relative to mean high water or ordinary high water mark) for all aerial crossings (bridges or overhead utility lines) over navigable water bodies
- Depth below bottom of water body for submarine utility crossings
- Dimensions of impoundment, dam, or stormwater management facility through a cross-section of the structure(s); bottom elevation(s) of basin created; depth of pool; and depth(s) to structure(s) on the bottom.
 - * Profile drawing or drawings with the information noted in Appendix D may be required by DEQ on a case-by-case basis to demonstrate minimization of impacts. When required, any application that proposes piping or culverting stream flows shall provide a longitudinal profile of the pipe or culvert position and stream bed thalweg, or shall provide spot elevations of the stream thalweg at the beginning and end of the pipe or culvert, extending to a minimum of 10 feet beyond the limits of proposed impact.







Boat Ramps







Dolphins or Moorings







Private Piers & Marginal Wharves







Boathouses










Breakwaters







Groins & Jetties







Filling Waters/Wetlands







Bulkheads and Associated Backfill







Dredging/Mining/Excavating







Nontidal Stream Channel Modifications







Intake/Outfall Structures







Beach Nourishment







Marsh Toe Stabilization







Riprap Revetment & Associated Backfill







Private & Commercial Aquaculture Activities







Road Crossings





Utility Crossings





Impoundment/Dams